



NOTES:

- RESTORE ALL DISTURBED SURFACES ABOVE AND SURROUNDING THE TRENCH TO EXISTING CONDITION AND ELEVATION. NATURAL GROUND WILL HAVE 6" OF TOP SOIL, SEEDED AND A RETENTION BLANKET INSTALLED ON TOP. ALL OTHER SURFACE STRUCTURES SHALL BE REPLACED TO MATCH EXISTING CONDITIONS.

REFERENCES
 DETAIL 510S-TD-SM

The City of San Marcos Engineering and Capital Improvements		CURRENT AS OF 1/1/2020	TRENCH DETAIL NATURAL GROUND	
RECORD COPY SIGNED BY <hr/> LAURIE MOYER, P.E.	6/1/2018 <hr/> ADOPTED	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.		STANDARD NO. 510S-5-SM 1 OF 1