

Item No. 705
Remove and Relocate Existing Metal Beam Guard Railing

705.1 Description

This item shall consist of removing and storing existing metal beam guard railing and posts and installing at the location indicated.

705.2 Materials

Materials will be those salvageable from the existing "Metal Beam Guard Railing" and any new materials required for the completion of the work as indicated. New materials shall meet the requirements of Item No. 704, "Metal Beam Guard Railing", unless those requirements are waived by the Engineer.

705.3 Construction Methods

The setting of posts and erection of the guard rail to be relocated as indicated shall be in accordance with the construction methods provided in Item No. 704, "Metal Beam Guard Railing".

All salvageable material not needed for the relocated "Metal Beam Guard Railing" shall be stored on the project site as directed by the Engineer.

705.4 Measurement

This item will be measured by the linear foot of rail, complete in its new location, measurement being made upon the face of the rail in place, from center to center of end posts.

705.5 Payment

The work performed and new materials furnished as prescribed by this item, measured as provided under "Measurement" will be paid for at the unit price bid for "Remove and Relocate Existing Metal Beam Guard Railing", which price shall be full compensation for removing, salvaging, storing and handling all existing guard rail material, digging post holes, furnishing concrete for post footings, for all manipulations, labor, tools, equipment and incidentals necessary to complete the work.

All salvageable material not used in the relocated "Metal Beam Guard Railing" will remain the property of the City and shall be stored on the project site as directed by the Engineer.

Payment will be made under:

Pay Item No. 705:	Remove and Relocate Existing Metal Beam Guard Railing	Per Linear Foot.
--------------------------	--	------------------

End

Ref: 704